

	INDICATES SIEVE TEST		INDICATES OBSERVED GROUNDWATER
TEST PIT # 1		GROUND EL. <u>103.61</u>	
ESHWG: <u>97.61</u>		TEST BY: <u>PATRICK H. CARRARA, III</u>	
DATE: <u>01/07/2020</u>		WITNESSED BY: <u>DOM RYDER</u>	
		CERTIFIED BY: <u>PATRICK H. CARRARA, III</u>	
*APPROVED SOIL EVALUATOR NUMBER SE338			

ELEVATION	SURFACE DEPTH (IN.)	SOIL HORIZ.	SOIL TEXTURE	SOIL COLOR	SOIL MOISTURE	OTHER
-103.61	0"-55"	Fill				FILL, ROOTS
-99.03	55"-61"	Ab	SANDY LOAM	10YR2/2		BURRED A HORIZON, ROOTS
-98.53	61"-81"	Bw	SANDY LOAM	10YR5/6		MEDIUM
-96.86	<div style="display: flex; align-items: center;"> 81"-132" </div>	C1	SANDY LOAM	5Y5/3	72" 30K 7.5YR 5/6 5Y 6/2	UNSORTED FINE COARS SATURATED, UNCOMPACT
-92.61	SOIL SAMPLE FOR SIEVE ANALYSIS TAKEN AT 90" ±					

WEEPING OBSERVED	81" EL.=96.86	PERC RATE	N/A	MIN/INCH
STANDING OBSERVED	N/A	PERC DEPTH	N/A	

1. 310 CMR 15.405(1)(g) REDUCE THE 100 FT. SETBACK FROM THE S.A.S. TO A PRIVATE ON-SITE POTABLE WELL TO 76 FT. UPGRADE REQUESTED BASED ON THE LIMITED AREA AVAILABLE TO SIT S.A.S. DUE TO THE PROXIMITY OF THE WETLANDS, PROPERTY LINE, AND EXISTING DWELLING.
2. 310 CMR 15.405(1)(i) TO ALLOW SIEVE ANALYSIS TO ESTABLISH SOIL CLASSIFICATION AND A PERCOLATION RATE APPROPRIATE FOR THE SOIL CLASS.
3. 310 CMR 15.405(1)(b) REDUCE THE 20 FT. SETBACK FROM THE S.A.S. TO THE EXISTING DWELLING TO 10 FT.
4. 310 CMR 15.405(1)(e) REDUCE THE 50 FT. SETBACK OF THE S.A.S. TO THE B.V.W. TO 31 FT.

CONSERVATION NOTE:
1. THE PROPOSED WORK IS WITHIN THE JURISDICTION OF THE CONSERVATION COMMISSION. WORK SHALL NOT COMMENCE UNTIL A NEGATIVE DETERMINATION OR ORDER OF CONDITIONS IS ISSUED BY THE CONSERVATION COMMISSION. ANY REQUIREMENTS AND/OR WORK REQUIRED BY THE COMMISSION'S DECISION SHALL BE INCLUDED IN THE SCOPE OF WORK.

ELEVATION SCHEDULE		ELEVATION (Ft.)
TOP OF FOUNDATION		106.46
NEW SEWER INVERT AT FOUNDATION		103.35
SEWER INVERT INTO SEPTIC TANK		103.14
SEWER INVERT OUT OF SEPTIC TANK		102.89
SEWER INVERT INTO D-BOX		102.57
SEWER INVERT OUT OF D-BOX		102.40
SEWER INVERT INTO LEACHING SYSTEM		102.28
TOP OF CHAMBER (BREAKOUT)		102.78
BOTTOM OF LEACHING FIELD		101.70
WATER TABLE (TP)		97.61

DESIGN FLOW 4 BEDROOMS x 110 GPD/BEDROOM = 440 GPD



SEPTIC TANK REQUIRED: 440 GPD x 200% = 880 GALLONS.
MIN. 1,500 GALLON SEPTIC TANK REQUIRED
MULTIPLE COMPARTMENT TANKS
FIRST COMPARTMENT / TANK:
48 HRS. HYDRAULIC DETENTION = 880 GAL
CAPACITY PROVIDED = 1,000 GAL
SECOND COMPARTMENT / TANK:
24 HRS. HYDRAULIC DETENTION = 440 GAL
CAPACITY PROVIDED = 500 GAL

LEACHING AREA REQUIRED: SIEVE ANALYSIS: 77.7% SAND, 8.6% SILT & 13.7% CLAY;
SANDY LOAM - CLASS II SOIL
USE EFFLUENT LOADING RATE OF 0.33* GPD/SF
440 GPD/0.33* GPD/SF=1,334 S.F.
* PER DEP POLICY "TITLE 5 ALTERNATIVE TO PERCOLATION TESTING GUIDANCE FOR SYSTEM UPGRADES"
EFFECTIVE DATE: MAY 3, 2006.

LEACHING AREA PROVIDED: 5 ROWS OF 11 ARC 36 CHAMBERS & 1 SIDE PORT COUPLER.
55 TOTAL CHAMBERS & 5 SIDE PORT COUPLERS.
5 ROWS @ 56.17' x 4.8* SF/LF= 1,348.08 S.F.
1,348.08 S.F. x 0.33 GPD/S.F. = 444.87 GPD
SINCE 444.87 GPD > 440 GPD O.K.

* EFFECTIVE LEACHING AREA PER TABLE 3 OF
CERTIFICATION FOR GENERAL USE ISSUED TO
INFILTRATOR WATER TECHNOLOGIES, LLC. ON JUNE
12, 2015 (TRANSMITTAL # X264258)

NOTE : SYSTEM NOT DESIGNED FOR USE WITH A GARBAGE GRINDER.



NOTES : 1.) NO STONE BELOW OR AROUND INFILTRATORS IS REQUIRED.
2.) BACKFILL INFILTRATORS WITH CLEAN COARSE SAND IN ACCORDANCE WITH 310 CMR 15.255 (3).
3.) DO NOT BACKFILL WITH ANY STONES 3" OR LARGER AGAINST INFILTRATOR.

Technical drawings of the dome cap assembly showing front, side, rear, and end views with dimensions:


- END CAP FRONT VIEW:** Shows the front profile of the dome cap with two circular openings.
- END CAP SIDE VIEW:** Shows the side profile of the dome cap.
- END CAP REAR/TOP VIEW:** Shows the rear/top profile of the dome cap with two circular openings.
- MAIN VIEW:** Shows the front view of the dome cap assembly with a width of 60" and a height of 34.5".
- POST END:** Shows the rear profile of the dome cap with a height of 13" and a 7.25" INVERT HEIGHT.
- DOME END:** Shows the dome profile of the dome cap.

Diagram illustrating the cross-section of a manhole structure, showing various components and elevations:


- TOP OF FOUNDATION EL.=106.46**
- FINISH GRADE = 105.2±**
- NEW 4" SCH 40 PVC INV=103.35**
- EL.=99.29**
- FOOTING**
- 4" SCH 40 PVC L=10.5 S=2X MIN**
- INV=103.14**
- NOT TO SCALE**
- RAISE COVER TO FINISH GRADE WITH WATER TIGHT RISERS AND SECURED MANHOLE COVERS.**
- FINISHED GRADE OVER TANK= 105.0±**
- TOP=104.22 ±**
- 4" INVE**
- 6" MIN.**
- AIR SPACE MIN. 6"**
- 10" MIN.**
- 4" DIA. HOLES**
- INSTALL 4"X18" ZL WITH GAS AND SUP**
- REINFORCED CONCRETE**
- GAS BATTLE (TYP.)**
- 4" SCH**
- INV=103**

SHEA "RESIDENTIAL 2-COMPARTMENT 1,500 GALLON SEPTIC TANK" OR EQUAL TO BE INSTALLED ON A LEVEL STABLE BASE. SEPTIC TANK TO BE INSPECTED & CLEANED ANNUALLY.

NOTES:
1. REMOVE AND REPLACE DOWN TO BOTTOM OF B-HORIZON ($EL=96.8\pm$). USE CLEAN
TITLE V SAND FOR REPLACEMENT MATERIAL, IF NECESSARY.



SOIL ABSORPTION SYSTEM
(14.375'W X 56.17'L LEACHING FIELD)




NOT TO SCALE

1. THIS PLAN HAS BEEN DESIGNED IN ACCORDANCE WITH TITLE 5 OF THE STATE SANITARY CODE, 310 CMR 15.000.
2. ALL SYSTEM COMPONENTS SHALL BE INSTALLED IN ACCORDANCE WITH TITLE 5 OF THE STATE SANITARY CODE, 310 CMR 15.000, AS AMENDED AND IN EFFECT AS OF SEPTEMBER 9, 2016, AND ANY LOCAL RULES APPLICABLE.
3. ANY CHANGE TO THIS PLAN MUST BE APPROVED IN WRITING BY THE DESIGN ENGINEER AND BOARD OF HEALTH.
4. BENCHMARK SHOWN ON PLAN IS TO BE VERIFIED BY THE CONTRACTOR. ANY DISCREPANCIES MUST BE RESOLVED WITH THE ENGINEER PRIOR TO CONSTRUCTION.
5. THIS SYSTEM IS NOT DESIGNED TO ACCOMMODATE A GARBAGE GRINDER.
6. SOIL CONDITIONS CAN VARY. GROUNDWATER ELEVATION AND THE LIMITS OF ACCEPTABLE SOIL MUST BE VERIFIED PRIOR TO INSTALLATION OF THE SOIL ABSORPTION SYSTEM (SAS).
7. LOCATIONS OF UTILITIES ARE APPROXIMATE. CONTRACTORS SHALL NOTIFY DIG SAFE (DIAL 811 OR 1-888-344-7233) AT LEAST 72-HOURS PRIOR TO BREAKING GROUND TO HAVE ALL EXISTING UTILITIES LOCATED AND CLEARLY MARKED.
8. ALL SYSTEM COMPONENTS TO BE H-10 RATED (MINIMUM).
9. HEAVY EQUIPMENT SHALL NOT BE ALLOWED TO OPERATE OVER THE LIMITS OF THE SEWAGE DISPOSAL SYSTEM DURING THE COURSE OF CONSTRUCTION OF THE SYSTEM.
10. BACKFILL OVER SAS MUST BE CLEAN AND FREE OF STONES >6 IN AND TAILINGS, CLAY OR SIMILAR MATERIALS. PLACE IN LIFTS AND SUFFICIENTLY COMPACT TO PREVENT DEPRESSIONS DUE TO SETTLING. MINIMUM 2% SLOPE REQUIRED OVER LEACHING AREA IN FINAL GRADING.
11. DESIGN ENGINEER TO BE NOTIFIED AT LEAST 48 HOURS PRIOR TO REQUIRED INSPECTIONS.
12. AN AS-BUILT SURVEY OF THE SYSTEM IS REQUIRED. ENGINEER AND BOARD OF HEALTH SHALL BE NOTIFIED FOR INSPECTION OF FIELD LOCATION PRIOR TO BACKFILLING/COVERING THE SYSTEM COMPONENTS. INSTALLER SHALL PROVIDE ENGINEER WITH RESULTS OF FILL SOIL SIEVE ANALYSIS BEFORE THE AS-BUILT CERTIFICATION WILL BE RELEASED.
13. THIS PLAN IS THE RESULT OF AN ON THE GROUND FIELD SURVEY BY THIS FIRM ON & BETWEEN 1/1/2020 & 2/5/2020
14. SUBJECT SITE IS NOT LOCATED WITHIN AN AREA OF CRITICAL ENVIRONMENTAL CONCERN (ACEC).
15. THERE ARE NO KNOWN OR PROPOSED WELLS WITHIN 100 FEET OF PROPOSED SAS EXCEPT AS INDICATED ON THIS PLAN.
16. WETLAND DELINEATION BY: ENVIRONMENTAL CONSULTING & RESTORATION, LLC. DELINEATION PERFORMED ON JANUARY 22, 2020.
17. CONTRACTOR IS RESPONSIBLE FOR OBTAINING ANY NECESSARY PERMITS.
18. CONTRACTOR SHALL MECHANICALLY COMPACT BASE UNDER SEPTIC TANK AND DISTRIBUTION BOX (IF INSTALLED IN FILL SOIL).
19. CONTRACTOR SHALL DECOMMISSION THE EXISTING SEPTIC SYSTEM COMPONENTS IN ACCORDANCE WITH 310 CMR 15.354, IF APPLICABLE.
20. CONTRACTOR SHALL RESTORE (LOAM & SEED) ALL AREAS DISTURBED DURING THE CONSTRUCTION.
21. LOCUS REFERENCE: DEED BOOK 54857, PAGE 324.
22. OWNER SHALL HAVE TANK INSPECTED AND/OR CLEANED ANNUALLY. ZABEL FILTERS SHALL BE CLEANED REGULARLY AND AT EACH TIME OF TANK PUMPING.
23. PROJECT BENCHMARK:
BENCHMARK A: NAIL IN UTILITY POLE-6 EL.=100.00 ASSUMED DATUM
BENCHMARK B: NAIN IN UTILITY POLE-7 EL.=107.57 ASSUMED DATUM
24. THE PROPERTY IS SERVED BY A PRIVATE ONSITE WELL. THE LOCATION OF THE WELL IS SHOWN.
25. THE SITE IS NOT LOCATED IN A ZONE II TO A PUBLIC WATER SUPPLY.

1. BOTTOM OF EXCAVATION;
2. TANK, PIPING, AND DISTRIBUTION BOX AND LINES PRIOR TO BACKFILLING;
3. FINAL COVER AND GRADING.

7. WITHIN AREAS SHOWN ON THE PLAN AS UNSUITABLE MATERIAL (E.G., TOPSOIL AND SUBSOIL) SHALL BE REMOVED AND REPLACED WITH FILL SOIL. CONSIST OF SELECT ON-SITE OR IMPORTED MATERIAL. THE FILL SOIL SHALL BE COMPRISED OF CLEAN GRANULAR SAND, FREE FROM ORGANIC MATERIAL AND DELETERIOUS SUBSTANCES. MIXTURES AND LAYERS OF DIFFERENT CLASSES OF SOIL SHALL NOT BE USED. THE FILL SHALL NOT CONTAIN ANY MATERIAL LARGER THAN TWO INCHES. A SIEVE ANALYSIS, USING A #4 SIEVE, SHALL BE PERFORMED ON A REPRESENTATIVE SAMPLE OF THE FILL. UP TO 45% BY WEIGHT OF THE FILL SAMPLE MAY BE RETAINED ON THE #4 SIEVE. SIEVE ANALYSES ALSO SHALL BE PERFORMED ON THE FRACTION OF THE FILL SAMPLE PASSING THE #4 SIEVE. SUCH ANALYSES WILL DEMONSTRATE THAT THE MATERIAL MEETS EACH OF THE FOLLOWING SPECIFICATIONS:

SIEVE SIZE	EFFECTIVE PARTICLE SIZE	% THAT MUST PASS SIEVE
# 4	4.75 MM	100%
# 50	0.30 MM	10% - 100%
#100	0.15 MM	0% - 20%
#200	0.075 MM	0% - 5%



1. CONCRETE: 4,000 PSI MINIMUM AFTER 28 DAYS.
2. DESIGN CONFORMS WITH 310 CMR 15.00, DEP TITLE 5 REGS. FOR SEPTIC TANKS.
3. ALL REINFORCEMENT PER ASTM C1227-93.
4. BAFFLE WALL OPTIONAL FOR TWO COMPARTMENT TANKS.
5. TEES AND GAS BAFFLE SOLD SEPARATELY.
6. TONGUE & GROOVE JOINT SEALED WITH BUTYL RESIN.
7. ALSO AVAILABLE IN H-20 LOADING.

ITEM NO.		WEIGHT
TK-1500	STANDARD	11,670
TK-1500H	H-20	13,135
TK-15002C	STANDARD	12,930
TK-15002CH	H-20	14,395

5-OUTLET DISTRIBUTION BOX WITH BAFFLE

2'-6 1/2"

1'-3 1/2"


1'-Box cover

2'-3"

10 1/2"

1'-5"

DESIGN NOTES:
1. CONCRETE 4,000 PSI @ 28 DAYS
2. KNOCK-OUT OPENINGS FOR 4" PV
3. 15" RISER SECTION AVAILABLE
4. H-10 & H-20 LOADING AVAILABLE

[illegible]


DRAWN BY:	MPJ/ALL
CHECKED BY:	GWD/EPJ
DESIGNED BY:	GWD

13 BLACKSTONE STREET
IN
MENDON
(WORCESTER COUNTY)
MASSACHUSETTS

FEBRUARY 20, 2020

PREPARED FOR:


SIMAR HOUSE, INC
102 MAPLE SPRINGS RD
WAREHAM, MA
02571



PMP

PMP Associates

200 North Bedford Street
East Bridgewater, Massachusetts 02333
Phone: 508-378-3421
www.pmpassoc.com



2/20/202

SHEET 1 OF 1

JOB NUMBER: 02-2019-047